BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT48594/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2021-22, Date: 01.10.2021

Name of Work:Maintaince and repairs of bore wells and providing pipeline in ward no.07 byatarayanpura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )	
				In Figures	In Words
1	1	Geophysical Investigation of site for sinking Borewell Geophysical Investigation of site for sinking Borewell for supplying drinking water to the habitation either through a hand pump, Mini Water Supply scheme, or Piped Water Supply Scheme by vertical electrical sounding by adopting venner or Schlumberger's method, including reconnaissance survey of geological formation, geophysical investigation of existing ground water in the vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation incluing an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc., complete and as per the directions of the Engineer-in-charge of the work.	Each	3333.04	Rupees Three Thousand Three Hundred Thirty Three and Four Paise Only
2	50	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete), complete and as per the directions of the Engineer-in-charge of the work .0-50mtrs	Rmtr	306.94	Rupees Three Hundred Six and Ninety Four Paise Only
3	50	50-100mtrs	Rmtr	390.98	Rupees Three Hundred Ninety and Ninety Eight Paise Only
4	50	100-150mtrs	Rmtr	403.36	Rupees Four Hundred Three and Thirty Six Paise Only
5	50	150-200mtrs	Rmtr	474.13	Rupees Four Hundred Seventy Four and Thirteen Paise Only
6	50	200-250mtrs	Rmtr	560.81	Rupees Five Hundred Sixty and Eighty One Paise Only
7	60	Supply of ISI Mark nominal bore, plain end steel casing pipe-grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest amendments, electrical resistance welded steel tube material and conforming to IS 1387- 1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5 to 7m. Both ends threaded conforming to IS 554-1985, one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes. All pipes shall be resonably free from defects. The tubes shall be resonably straight and should be with ISI marking weighing 25.10kg/m. (exclusive of all taxes and duties). Prices include Collar-Medium duty 175mm dia x 5.4mm thick - Rs.950.00 complete and as per the directions of the Engineer-in-charge of the work.	Rmtr	1172.05	Rupees One Thousand One Hundred Seventy Two and Five Paise Only
8	10	PVC Pipes 10kg/sqm 250mm outerdia	m	1892.27	Rupees One Thousand Eight Hundred Ninety Two and Twenty Seven Paise Only
9	1	Providing and laying at site of work MS casing caps as per IS 1239 (part-II) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments including cost of material and labour charges for fixing, if any etc. complete with all lead and lifts and as directed by the Engineer in charge	Each	88.46	Rupees Eighty Eight and Forty Six Paise Only

Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )	
				In Figures	In Words
10	20000	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work.	Sqm	0.3	and Thirty Paise Only
11	1	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI union confirming to IS 1239-II, 1991 with latest amendments if any.	No	154.8	Rupees One Hundred Fifty Four and Eighty Paise Only
12	3	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI hexagonal nipple confirming to IS 1239-II, 1991 with latest amendments if any.	No	123.84	Rupees One Hundred Twenty Three and Eighty Four Paise Only
13	3	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI elbow confirming to IS 1239-II, 1991 with latest amendments if any.	No	154.8	Rupees One Hundred Fifty Four and Eighty Paise Only
14	1	Labour charges for Erection, Electrification and commissioning works of Pump sets including aligning and balancing with all necessary erection of materials and labour including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges, tools and equipments etc., involved in the job. as per specifications, with testing of as per instructions of engineer incharge of work	No	4997.79	Rupees Four Thousand Nine Hundred Ninety Seven and Seventy Nine Paise Only
15	1	Labour charges for Erection of outdoor type panel board and meter board units with all necessary materials and labour tools and equipments including providing cement concrete foundation bed etc., complete. as per specifications, with testing of as per instructions of engineer incharge of work	No	1059.71	Rupees One Thousand Fifty Nine and Seventy One Paise Only
16	30	Supplying of 1.1KV LT UG cable XPLE or heat resistant PVC Insulated PVC eatruded inner sheath armoured UG LT cable as per IS -1554(Part-1) or IS-7098 Part-1,Armouring strip thickness in average +5% and resistivity 14ohms/kms(max) as per IS -3975 4 core 16sqmm	Rmtr	128.82	Rupees One Hundred Twenty Eight and Eighty Two Paise Only
17	30	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stone pipe / on wall/ on pole as required 6 sqmm to 16 sqmm.	Rmtr	10.2	Rupees Ten and Twenty Paise Only
18	30	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete cutting road surfaces	Mtr	70.42	Rupees Seventy and Forty Two Paise Only
19	4	Supplying and fixing of class A GI pipe on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm	Mtr	287.7	Rupees Two Hundred Eighty Seven and Seventy Paise Only
20	1	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia.	Nos	3213.62	Rupees Three Thousand Two Hundred Thirteen and Sixty Two Paise Only
21	1	Providing, Supplying and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.with all necessary materials and labour tools and equipments . as per specifications, with testing of as per instructions of engineer incharge of work a) 3x6 Sqmm	Nos	439.63	Rupees Four Hundred Thirty Nine and Sixty Three Paise Only
22	1	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc.,Size 20 x 20 x 2.5 inches with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	250.77	Rupees Two Hundred Fifty and Seventy Seven Paise Only
23	1	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 20 HP 40 Stage	Nos	77802.99	Rupees Seventy Seven Thousand Eight Hundred Two and Ninety Nine Paise Only

Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )	
				In Figures	In Words
24	59	Supply and delivery of galvanized mild steel tubes of 6 mtr standard length heavy class (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with heavy duty collar and other end fitted with protective cover) (50mm)	Rmtr	2457.32	Rupees Two Thousand Four Hundred Fifty Seven and Thirty Two Paise Only
25	600	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990.complete and as per the directions of the Engineer-in-charge of the work.	Mtr	174.31	Rupees One Hundred Seventy Four and Thirty One Paise Only
26	1	Supplying & delivery at site brand new / Essen / lotus sunsines/Adarsh/Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph,50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz,380/440 AC supply shall be consisted etc., completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above Up to 20HP with star delta starter (MR)	Nos	18034.8	Rupees Eighteen Thousand Thirty Four and Eighty Paise Only
27	1	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments a)size 50mm	Each	1052.63	Rupees One Thousand Fifty Two and Sixty Three Paise Only
28	1	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments a)size 50mm	Each	1039.36	Rupees One Thousand Thirty Nine and Thirty Six Paise Only
29	1	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box.	Each	906.68	Rupees Nine Hundred Six and Sixty Eight Paise Only
30	9.99	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications For Connecting borewell	Cum	272.19	Rupees Two Hundred Seventy Two and Nineteen Paise Only
31	37	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including joining of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete For Connecting borewell	Mtr	108.8	Rupees One Hundred Eight and Eighty Paise Only
32	9.99	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications For Connecting borewell	Cum	110.15	Rupees One Hundred Ten and Fifteen Paise Only
33	2.5	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc. in the following classification. (RDWS SR 2019-20 Pg No.08 I No.2.26) Cutting Asphalt Road Surface	Cum	493.5	Rupees Four Hundred Ninety Three and Fifty Paise Only
34	7.63	Earthwork excavation in soil, clay, sand, shedu soil, soft murrum, including shoring, strutting, barricading, danger lighting, bailing out water wherever necessary with stacking the materials as directed upto a lead of 50 Mtr and lift of 1.5 Mtr etc., complete. For Water Recharge Pits,	Cum	306.06	Rupees Three Hundred Six and Six Paise Only
35	3.82	Add for additional lift charges for every lift of 1.50 M or part thereof beyond 1.50 Mtr to 10.50 Mtr For Water Recharge Pits,	Cum	50.42	Rupees Fifty and Forty Two Paise Only
36	0.08	Providing and laying in position plain cement concrete of grade M 10 with cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregtes @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, including cost of all materials, labour, HOM of machinery, curing,lowering to any depth, dewatering etc., complete as per specifications with all lead and lifts for Foundation of steining. For Water Recharge Pits,	Cum	5336.57	Rupees Five Thousand Three Hundred Thirty Six and Fifty Seven Paise Only

U. Ramesh

Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )	
				In Figures	In Words
37	0.68	100 mm and down nominal size For Water Recharge Pits,	Cum	873.61	Rupees Eight Hundred Seventy Three and Sixty One Paise Only
38	1.87	40 mm nominal size stone aggregates RCC Pits,	Cum	965.45	Rupees Nine Hundred Sixty Five and Forty Five Paise Only
39	0.68	20 mm nominal size stone aggregates RCC Pits,	Cum	965.45	Rupees Nine Hundred Sixty Five and Forty Five Paise Only
40	0.68	6 mm nominal size stone aggregates	Cum	965.45	Rupees Nine Hundred Sixty Five and Forty Five Paise Only
41	0.57	KSRB 2.6: Providing and filling sand RCC Pits,	Cum	1486.92	Rupees One Thousand Four Hundred Eighty Six and Ninety Two Paise Only
42	10	Supplying & errection of RCC rings for well steining of 0.3 Mtr Depth using M-20 grade concrete using clean graded granite or trap or jelly of approved quality 20mm and down size well compacted including centering, formwork and plastering for both faces with C.M 1:3 proportion as per design using 6.50mm M.S. coil at the rate of 10 Kgs/ring including cost of steel and fabrication, bailing out of water, errection etc., complete. For 1.20m dia (clear) rings of steining thickness 0.075mm upto 18 M depth RCC Pits,	Each	980.99	Rupees Nine Hundred Eighty and Ninety Nine Paise Only
43	23.73	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM complete as per specifications. Specification No.KBS 7.12 RCC Pits,	Kgs	86.5	Rupees Eighty Six and Fifty Paise Only

U. Ramesh

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92